

BILL NO.: 4869

ORDINANCE NO.: _____

Introduced by: Council Present

AN ORDINANCE OF THE CITY OF BERKELEY, MISSOURI, AUTHORIZING THE ASSISTANT CITY MANAGER TO EXECUTE AN AGREEMENT WITH SPENCER CONTRACTING FOR ROAD REPAIR ON LANGDON CT & FRIARWOOD DR (*The City Council Does Hereby Find and Declare that an Emergency Exists Which Requires the Immediate Passage of this Ordinance for the Preservation of the Welfare of the Citizens of the City of Berkeley.*)

NOW, THEREFORE, BE IT ORDAINED BY THE CITY COUNCIL OF THE CITY OF BERKELEY, MISSOURI, AS FOLLOWS:

- Section 1.** That the Assistant City Manager is hereby authorized to enter into and execute an agreement with Spencer Contracting to complete emergency slab work repair on Langdon Court and Friarwood Drive.
- Section 2.** The agreement will be attached and hereby incorporated herein and made a part of this ordinance, as if fully set out herein.
- Section 3.** This Ordinance shall be in full force and effect from and after its passage.
- Section 4.** The City Council does hereby find and declare that an emergency exists which requires the immediate passage of this ordinance for the preservation of the welfare of the citizens of the City of Berkeley.

1st Reading this _____ day of _____ 2022

2nd Reading this _____ day of _____ 2022

3rd Reading, PASSED and APPROVED, this _____ day of _____ 2022

Babatunde Deinbo, Mayor

ATTEST:

Deanna L. Jones, City Clerk

Approved as To Form:
Donnell Smith, City Attorney

Final Roll Call:

Councilwoman Mitchell	Aye ___	Nay ___	Absent ___	Abstain ___
Councilwoman Williams	Aye ___	Nay ___	Absent ___	Abstain ___
Councilwoman Hoskins	Aye ___	Nay ___	Absent ___	Abstain ___
Councilwoman Anthony	Aye ___	Nay ___	Absent ___	Abstain ___
Councilman Hindeleh	Aye ___	Nay ___	Absent ___	Abstain ___
Councilwoman-at-Large Greene	Aye ___	Nay ___	Absent ___	Abstain ___
Mayor Deinbo	Aye ___	Nay ___	Absent ___	Abstain ___



3073 Arnold Tenbrook Rd, Arnold MO 63010

314-843-5166 – PHONE

314-843-6106 – FAX

Proposal Submitted to: City of Berkeley

Date: 03/30/2022

Job: Langdon Ct & Friarwood Drive Slab
Replacement

PROPOSAL

We hereby submit specifications and estimate for: Concrete Street Replacement

INCLUSIONS

- Full Depth Saw cut slabs as needed to remove.
- Break concrete, excavate and remove to a depth of 11 inches.
- Compact sub grade and add 4 inches of type 5 base rock.
- Rock to be rolled to proper compaction.
- Form and pour with 5000 psi PCCP concrete 7" thick.
- Rolled curbs to be poured monolithically with street pavement.
- Slabs will be doweled into existing slabs.
- Control Joints to be spaced appropriately. Expansion joints as necessary.
- Concrete to be broom finished.
- Spencer to provide construction signs and trim lines to properly barricade work zone.
- Backfill, seed, and straw behind curb.
- All spoils to be properly disposed of.
- Langdon Ct is 102' x 13' and Friarwood 42' x 13'
- Utility Locates to be called in prior to excavation by Spencer.


Total to Complete: \$27,600.00

Payment to be made in Full upon completion.

All work to be completed in a workmanlike manner according to standard practices. Any alteration or deviation from above specifications involving extra costs, will be executed only upon written orders, and will become an extra charge over and above the estimate. This proposal subject to acceptance within 14 days and is void thereafter at the option of the undersigned.

Signatures Required for Acceptance of Proposal:

The above prices, specifications and conditions are satisfactory and are hereby accepted. Spencer Contracting Company is authorized to do the work as specified. Payment will be made as outlined above.


Spencer Contracting Company

3/30/2022
Date



Fairwood @ Midwood Two Slabs
42'X13'



6200 BIK
Langdon Ct.

Five Slabs
102' X 13'

Concrete